

INTERNATIONAL INDUSTRY EXPO 2024 Industrial Development Board of Ceylon Bill of Quantities -T/05/2024					
For the All Utilities of Five Days Exhibition (19,20,21,22 & 23 of June 2024 )					
No	Description	Quantity	Unit	Unit Price for 5 days Period (Rs.)	Total value (Rs.)
<b>Note:</b> Bidders shall carefully observe the stall/canopy layout plans,instructions provided in prebid meeting and notes before completing this boq.					
<b>NORMAL MARQUEES</b>					
1	Supply ,installation,removal after exhibition of fully open pre fabricated "A" shaped German marquee ( side covers should be closable when ever required) with suitable entrance and exists including floor decks with floor carpet.				
1.1	Western Car park Tent (Hall - F1) - 65' x 20'	1,300			
1.2	Western Car Park Tent ( Hall - F2) - 100' x 20'	2,000			
1.3	Gate 4 Grass area Tent ( Hall - S1) - 170' x66'	11,220			
1.4	Gate 4 Grass area Tent ( Hall - S3) - 150'x 50'	7,500			
1.5	Gate 4 Grass area Tent ( Hall - S4) - 130'x 30'	3,900			
1.6	Main Car Park Tent ( Hall -T1) - 280' x 30'	8,400			
1.7	Main Car Park Tent ( Hall -T2) - 280' x 33'	9,240			
1.8	Main Car Park Tent ( Hall -T3) - 250' x 30'	7,500	Sqft		
1.9	Main Car Park Tent ( Hall -T4) - 200' x 50'	10,000			-
1.10	Hall W1-(90'*20')	1,800			
1.11	Hall W2-(90'*20')	1,800			
1.12	Hall W3-(110'*20')	2,200			
1.13	Hall W4-(100'*20')	2,000			
1.14	Hall W5-(100'*20')	2,000			
1.15	Hall W6-(80'*20')	1,600			
<b>Total of Page No. 01 carried to Summary in Page No. 07</b>					

INTERNATIONAL INDUSTRY EXPO 2024 Industrial Development Board of Ceylon Bill of Quantities -T/05/2024					
For the All Utilities of Five Days Exhibition (19,20,21,22 & 23 of June 2024 )					
No	Description	Quantity	Unit	Unit Price for 5 days Period (Rs.)	Total value (Rs.)
<b>AIR CONDITIONED MARQUEES</b>					
2	Supply ,installation,dismantelling and removal after exhibition of fully covered, <b>Air conditioned</b> pre fabricated "A" shaped German marquee with suitable entrance and exists including floor decks with floor carpet. (Following criteria should be maintained for Air Conditioned canopy , 1.Temperature range 18 °C-24 °C. 2.No special heat source permitted in A/C Stalls. 3.LED lighting to be considered 4.Air Curtains should be installed at the entrances and exists) (Attach A/C unit placement layout with the bid) Testing & commissioning should complete at 12 pm before exhibition starting date and 4 hours test run to be done to ensure the expected delivery.			..	
	Note: All Air conditioners should be connected to a distribution board with all necessary accessories including main cable from power source(i.e generator breaker or inbuild DB of the main Hall.) Make a suitable arrangement for effectively cooling central walking paths/entire marquee using air conditioners or an airconditioned ducting system.				
2.1	Hall -C (150' x 66')	9,900			
2.2	Outer Gate Grass Area Hall - D (350' x 66')	23,100			
2.3	Hall E (100' x 50')	5,000			
2.4	Western Car Park Area Hall - G (150' x 100')	15,000			
2.5	Western Car Park Area Hall - H1 (145' x 33')	4,785			
2.6	Western Car Park Area Hall - H2 (65' x 50')	3,250			
2.7	Mihilak Medura Hall - K (100' x 40')	4,000	Sqft		
2.8	Open Air Hall - L (250' x 66')	16,500			
2.9	Hall - P (80' x 40')	3,200			
2.10	Nugasewana -M (50'*150')	7,500			
2.11	Gate 4 Grass Area Hall - S2 (100' x 50')	5,000			
2.12	Hall U (350'*50')	17,500			
2.13	Supply ,installation,dismantelling and removal after exhibition of fully covered, <b>Air conditioned</b> pre fabricated "A" shaped German marquee with suitable entrance and exists including floor decks with floor carpet and 02 tables,chairs and visitor sofa furniture. ( Near smack outlet) 1.Operation Tent -10' x 20'	200	sqft		
<b>Total of Page No. 02 carried to Summary in Page No. 07</b>					

INTERNATIONAL INDUSTRY EXPO 2024 Industrial Development Board of Ceylon Bill of Quantities -T/05/2024					
For the All Utilities of Five Days Exhibition (19,20,21,22 & 23 of June 2024 )					
No	Description	Quantity	Unit	Unit Price for 5 days Period (Rs.)	Total value (Rs.)
<b>TRADE STALLS</b>					
3	Supply , installation ,dismantle and removal of pre fabricated stalls having the size of <b>3m x 3m</b> as per the stall plan including followings. (Rate shall be included for followings.) 01 number of counter table (3' x2') & 02 number of plastic chairs within the given time period.(Tables and chairs should be placed in the stalls).	940	Nos		
4	Supply , installation ,dismantle and removal of pre fabricated stalls having the size of <b>2m x 2m</b> as per the stall plan including followings. (Rate shall be included for followings.) 01 number of counter table (3' x2') with <b>black table cloths</b> & 02 number of plastic chairs within the given time period.(Tables and chairs should be placed in the stalls).	60	Nos		
<b>LIGHTING &amp; POWER SUPPLY FOR STALLS</b>					
5	Note: All installation should connected to a distribution board with all necessary accessories including main cable from power source(i.e generator breaker or inbuild DB of the main Hall). 1).Supply and install (including wiring) suitable 15 W spot lights to illuminate stalls (Two nos for one stall) Pls Note - All wires on the floor area of all halls should be covered by PVC conduit pipes as per the IEE safety guidelines. 2).Supply and install (including wiring) 13A socket outlets to powerup stalls as required (1 number for 1 stall) IEE safety guidelines.	1,315	Nos		
<b>MAINTENANCE STAFF ALLOCATION</b>					
6	Providing <b>Electrical &amp; Air Conditioning maintenance staff</b> to carried out all construction and maintenance work from the day before exhibition to end date of the exhibition (Team atleast consist of one skilled technician and one helper. They are required to sign in on an hourly basis to indicate their presence.) <b>Note</b> - Need separate teams dedicated to maintenance, distinct from the installation team.				
6.1	Electrical maintenance teams-	12	Nos		
6.2	Air Conditioning maintenance teams-	5	Nos		
Total of Page No. 03 carried to Summary in Page No. 07					

INTERNATIONAL INDUSTRY EXPO 2024 Industrial Development Board of Ceylon Bill of Quantities -T/05/2024					
For the All Utilities of Five Days Exhibition (19,20,21,22 & 23 of June 2024 )					
No	Description	Quantity	Unit	Unit Price for 5 days Period (Rs.)	Total value (Rs.)
<b>EXTERNAL LIGHTING</b>					
Note: All installation should connected to a distribution board with all necessary accessories including main cable from power source(i.e generator breaker or inbuild DB of the main Hall.					
7	Supply and install (including wiring) <b>100 W LED</b> light IP68 to illuminate covering the land area around the marquee areas.	100	Nos		
8	Design supply and install (including wiring) <b>30 W LED</b> reflector lights to illuminate tent and other areas sufficiently.	565	Nos		
9	Design supply and install (including wiring) 3W 54 LED's RGB <b>power can lights</b> for garden areas according to layout requirements	200	Nos		
10	Supply and install (including wiring) 13A socket outlet to powerup open spaces , 30 W LED reflector light to illuminate space (1 number of each for 1 space)	19	Nos		
11	Design supply and install (including wiring) moving heads lights for garden areas/building according to layout requirements	20	Nos		
<b>ENTRANCE GATE PANDOLS/VIDEO WALLS</b>					
12	Supply and install exhibition area <b>main entrance pandol</b> (over the road) according to the main theme.	1	Nos		
13	Supply and install exhibition area <b>sub entrance pandol</b> (over the road) according to the main theme.	2	Nos		
14	Supply of PA system covering the BMICH premises and surrounding area ( including horn speaker,tops and bins,cabling,mics & necessary instuments.)	1	Item		
15	06'X10' P-4 Outdoor Quality LED Strips with supporting structures placed along both sides of the main entrance road including Multi Screen Continue Playback System.	16	Nos		
16	Supply and Fixing of digitally printed flex banners size of 06'X10'with supporting structures placed along both sides of the main entrance road	16	Nos		
17	12'X8' P-4 Outdoor Qualit LED wall including necessary instumentations with supporting structures	3	Nos		
<b>Total of Page No. 04 carried to Summary in Page No. 07</b>					

INTERNATIONAL INDUSTRY EXPO 2024 Industrial Development Board of Ceylon Bill of Quantities -T/05/2024					
For the All Utilities of Five Days Exhibition (19,20,21,22 & 23 of June 2024 )					
No	Description	Quantity	Unit	Unit Price for 5 days Period (Rs.)	Total value (Rs.)
<b>ORGANIZING AND CONDUCTING OF INNOGORATION CEREMONY ON LOBBY OF SIRIMAVO HALL FOR 05 DAYS</b>					
18	40'X13' P-3 High Defenition Quality Indoor OpenableLED Screen -(5 Days during exhibition hours)	1	Nos		
19	Surrounding Sound System for Innogoration Area-(5 Days during exhibition hours)	1	Item		
20	Effect Lights & Color wash Light System for Innogoration Area-(5 Days during exhibition hours)	1	Item		
21	Conceptualized Dance Act according to the theme-(Only for 1 <sup>st</sup> day innogoration)	1	Item		
22	Kandian Dance Team-(Only for 5 day innogoration)	1	Item		
23	Stage for Innogoration Area (keep ready for the occation)	1	Item		
24	VIP Chairs (keep ready for the occation)	40	Nos		
25	Black Curatin Covering for lobby area	1	Item		
26	Providing Media Unit Innogoration Ceremony	1	Item		
27	Supply and decorate podium with flora arrangement	1	Nos		
28	Supply ,install and function 16' x 10' P-3 indoor LED Screen for display adds including playback system for both sides of the sirimawo entrance	2	Nos		
<b>Total of Page No. 05 carried to Summary in Page No. 07</b>					

INTERNATIONAL INDUSTRY EXPO 2024 Industrial Development Board of Ceylon Bill of Quantities -T/05/2024					
For the All Utilities of Five Days Exhibition (19,20,21,22 & 23 of June 2024 )					
No	Description	Quantity	Unit	Unit Price for 5 days Period (Rs.)	Total value (Rs.)
<b>BMICH MAIN HALL SYMPOSIUM-2 Days</b>					
29	30'X15' P-3 High Defenition Quality Indoor LED Screen with required instruments	1	Nos		
30	Surrounding Sound System with 5 FM Mics	1	Item		
31	Glass top tables for stage	2	Nos		
32	VIP Chairs	5	Nos		
33	Floor arrangements for podium & oil lamp	1	Item		
<b>T-SHIRT PRINTING</b>					
34	Design, print & Supply of Exhibition branding T shirts	800	Nos		
<b>TICKETING</b>					
35	Make arrangements for ticketing counters to control unauthorized entry from other entrances with tents for ticketing counters including tables and chairs(10'*20' marquee)	3	Nos		
Total of Page No. 06 carried to Summary in Page No. 07					

Note:

- The contractor shall Provide full time maintenance staff to attend all kinds of emergencies arise in all the services (Civil,Electrical ,Mechanical,Sound System And Etc.)